

MODULAR HOPPER BARGE



EAST COAST
MARINE CONTRACTING

MODULAR HOPPER BARGE



General

Name	Modular Hopper Barge
Type	Modular Construction Hopper Barge
Operator	East Coast Marine Contracting
Survey	AMSA 2D
Construction	Steel
Road Transport	Yes

Main Dimensions

Length Overall	12.192 meters
Width/Beam	9.144 meters
Depth	2.13 meters
Hopper Capacity	80m ³

Operation:

ECMC own and operate a Modular Hopper Barge consisting of three Modular Construction Barges with an 80m³ hopper built into the middle barge to minimise air draft. The Modular Hopper Barge is ideal for dredging and material storage including muck cuttings from drilling and piling operations.

Three standard semi trailers are required to mobilise the barge.

EAST COAST MARINE CONTRACTING

PO BOX 547, Caringbah NSW 1495

Phone: 0405 835 762 Email: dane@eastcoastmarinecontracting.com.au